


Y




LONGITUDINAL SECTION

ELEVATION VIEW @ GRIDLINE A

A
14A CB

SCALE 1:180




LONGITUDINAL SECTION

ELEVATION VIEW @ GRIDLINE B

B
14A CB

SCALE 1:180




LONGITUDINAL SECTION

ELEVATION VIEW @ GRIDLINE C

SCALE 1:180

A
14B CB




LONGITUDINAL SECTION

ELEVATION VIEW @ GRIDLINE D


SCALE 1:180

B
14B CB




A
140 CB

LONGITUDINAL SECTION
ELEVATION VIEW @ GRIDLINE E
SCALE 1:180



B
140 CB

LONGITUDINAL SECTION
ELEVATION VIEW @ GRIDLINE F
SCALE 1:180




CROSS SECTION

ELEVATION VIEW @ GRIDLINE 1

A
14D CB

SCALE 1:180




CROSS SECTION

ELEVATION VIEW @ GRIDLINE 2

B
14D CB

SCALE 1:180




CROSSL SECTION

ELEVATION VIEW @ GRIDLINE 3

C
14D CB


SCALE 1:180



CROSS SECTION

ELEVATION VIEW @ GRIDLINE 4


SCALE 1:180



CROSS SECTION

ELEVATION VIEW @ GRIDLINE 5


SCALE 1:180



CROSS SECTION

ELEVATION VIEW @ GRIDLINE 6

SCALE 1:180




CROSSL SECTION

ELEVATION VIEW @ GRIDLINE 7

SCALE 1:180

A
14F CB



A 03 CB **FOUNDATION PLAN**

SCALE 1:140

NOTES: (U.O.S. – UNLESS OTHERWISE STATED)


1. ALL DIMENSIONS ARE IN MILLIMETER, U.O.S.
2. U.O.S., ALL CHB PARTITION SHALL REST ON WALL FOOTINGS.
3. U.O.S., RC PEDESTALS SHALL BE PROVIDED WHERE COLUMNS ARE IN DIRECT CONTACT WITH THE EARTH. THE MINIMUM DIMENSION OF THE PEDESTALS SHALL BE 50mm BIGGER THAN THE COLUMN DIMENSION, MAINTAINING A MINIMUM OFFSET OF 25mm FROM COLUMN FACE.
4. THE DESIGN NET ALLOWABLE SOIL BEARING CAPACITY USED IS 427 kPa AT MINIMUM FOUNDING LEVEL OF 2.00m (@ CUT AREA) AND 407 kPa AT MINIMUM FOUNDING LEVEL OF 1.00m (@ FILL AREA) BELOW NATURAL GRADE BASED ON BOREHOLE BH-04 OF GEOTECHNICAL REPORT.
5. SITE ADAPTATION: THE GENERAL CONTRACTOR SHALL INFORM THE STRUCTURAL ENGINEER OF ANY SITE CONDITION THAT MAY REQUIRE CHANGES IN THE STRUCTURAL DESIGN.
6. FOR FOUNDATION DETAILS REFER TO SHEET NO. 04
7. FOR TIE BEAMS REINFORCEMENT REFER TO BEAM SCHEDULE AT SHEET NO. 09
8. REFER TO SITE DEVELOPMENT PLAN AND CIVIL WORKS DRAWINGS FOR THE DETAILS OF CABLE TRENCH.
9. U.O.S., THE TOP ELEVATION OF TIE BEAMS IS +0.25.

LEGEND:

TB	TIE BEAM MARK
WF-1	WALL FOOTING MARK
F1/C1	FOOTING/ COLUMN MARK
S.S.L.	STRUCTURAL SLAB LEVEL
F.G.L.	FINISH GRADE LINE

FOOTING SCHEDULE

FOOTING MARK	FOOTING DIMENSION (mm)			TOP REINFORCEMENT		BOTTOM REINFORCEMENT	
	DIM. "B"	DIM. "L"	DIM. "T"	BAR "A"	BAR "B"	BAR "C"	BAR "D"
F1	2400	2400	500	–	–	ø16 @ 150mm	ø16 @ 150mm
F2	2100	2100	500	–	–	ø16 @ 150mm	ø16 @ 150mm
F3	1900	1900	450	–	–	ø16 @ 150mm	ø16 @ 150mm
F4	1750	1750	450	–	–	ø16 @ 150mm	ø16 @ 150mm
F5	2900	2900	450	–	–	ø16 @ 150mm	ø16 @ 150mm
CF1	2200	4600	600	ø32 @ 125mm	ø16 @ 150mm	ø16 @ 100mm	ø16 @ 150mm
MF–1	4200	4600	650	ø16 @ 100mm	ø16 @ 100mm	ø16 @ 100mm	ø16 @ 100mm
MF–2	5500	5500	650	ø16 @ 100mm	ø16 @ 100mm	ø20 @ 100mm	ø20 @ 100mm




A 04 CB **SECTION 1**


SCALE NTS

NOTES: (U.O.S. – UNLESS OTHERWISE STATED)


1. ALL DIMENSIONS ARE IN MILLIMETER, U.O.S.
2. U.O.S., ALL CHB PARTITION SHALL REST ON WALL FOOTINGS.
3. U.O.S., RC PEDESTALS SHALL BE PROVIDED WHERE COLUMNS ARE IN DIRECT CONTACT WITH THE EARTH. THE MINIMUM DIMENSION OF THE PEDESTALS SHALL BE 50mm BIGGER THAN THE COLUMN DIMENSION, MAINTAINING A MINIMUM OFFSET OF 25mm FROM COLUMN FACE.
4. THE DESIGN NET ALLOWABLE SOIL BEARING CAPACITY USED IS 427 kPa AT MINIMUM FOUNDING LEVEL OF 2.00m (@ CUT AREA) AND 407 kPa AT MINIMUM FOUNDING LEVEL OF 1.00m (@ FILL AREA) BELOW NATURAL GRADE BASED ON BOREHOLE BH–04 OF GEOTECHNICAL REPORT.
5. SITE ADAPTATION: THE GENERAL CONTRACTOR SHALL INFORM THE STRUCTURAL ENGINEER OF ANY SITE CONDITION THAT MAY REQUIRE CHANGES IN THE STRUCTURAL DESIGN.
6. FOR TIE BEAMS REINFORCEMENT REFER TO BEAM SCHEDULE AT SHEET NO. 09
7. REFER TO SITE DEVELOPMENT PLAN AND CIVIL WORKS DRAWINGS FOR THE DETAILS OF CABLE TRENCH.



TYPICAL PLAN OF RC FOOTING (NON–ECCENTRIC)




TYPICAL PLAN OF RC COMBINED FOOTING



B 04 CB **SECTION 2**


SCALE NTS




SCALE NTS

TYP. DETAIL OF WALL FOOTING (WF-1)


D 04 CB



SECTION A–A (TYPICAL FOOTING)




SECTION A–A (FOOTING @ FILL)



SECTION B–B

E 04 CB **TYP. DETAILS OF FOUNDATION**

SCALE NTS



C 04 CB **SECTION 3**


SCALE NTS

NOTES:


1. ALL DIMENSION ARE IN MILLIMETERS, U.O.S.
2. ALL CONNECTION ARE WELDED UNLESS OTHERWISE NOTED.
3. MINIMUM THICKNESS OF WELD = 3mm UNLESS OTHEWISE NOTED.
4. U.O.S., ALL STRUCTURAL STEEL MEMBERS SHALL CONFORM TO ASTM SPECIFICATIONS FOR A-36 STEEL.

SECTION MEMBERS:


① = 200x50x5mm TUBULAR
② = 250x88x5mm TUBULAR




A 13 CB STEEL CANOPY SF-1 PLAN
SCALE 1:50




B 13 CB STEEL CANOPY SF-2 PLAN
SCALE 1:50






C 13 CB SECTION
SCALE NTS




D 13 CB DETAIL B
SCALE NTS




M16 x 200 BOLT DETAIL


E 13 CB DETAIL A
SCALE NTS



VIEW A




SECTION 1.1



ø16MM x 400 BOLT DETAIL


NOTES:

1. ALL DIMENSION ARE IN MILLIMETERS, U.O.S.
2. ALL CONNECTION ARE WELDED UNLESS OTHERWISE NOTED.
3. MINIMUM THICKNESS OF WELD = 3mm UNLESS OTHEWISE NOTED.
4. U.O.S., ALL STRUCTURAL STEEL MEMBERS SHALL CONFORM TO ASTM SPECIFICATIONS FOR A-36 STEEL.



SECTION MEMBER:

(1) = 200x50x5mm TUBULAR



SECTION 1.1

B
14 CB
SECTION
SCALE 1:60

16MM DIA. BOLT DETAIL