ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
	C.	**CIVIL WORKS**										
	C.1	**COMPLETE DESIGN, FURNISH, INSTALL, SUPPLY, PROVIDE, ERECT, MODIFICATION, PLACE, APPLY AND/OR LAY INCLUDING FURNISHING OF ALL PLANT, LABOR, EQUIPMENT AND MATERIALS OF THE FOLLOWING ITEMS OF WORKS IN ACCORDANCE WITH THE PROVISIONS IN THE TENDER DOCUMENTS. DESIGN OF FOUNDATION SHALL BE BASED ON THE GEOTECHNICAL REPORT PROVIDED BY NGCP. ALL WORKS SHALL BE IN COMPLIANCE WITH NGCP CONSTRUCTION QUALITY AND WORKMANSHIP STANDARD:**										
	1.	**Site Grading**										
SS1	a.	Clearing and grubbing	1	lot	1	1	1	1	1	1	3	3
SS1	b.	Stripping	1	lot	N/A	N/A	N/A	N/A	N/A	N/A		
SS1	c.	Grading Fill	1	lot	N/A	N/A	N/A	N/A	N/A	N/A		
SS1	d.	Grading Excavation (Unclassified)	1	lot	N/A	N/A	N/A	N/A	N/A	N/A		
	2.	**Drainage System**										
SS1	a.	Pipes	1.00	lot							1,903,314.55	1,903,314.55
		300mm Ø (12")	386.00	m				1,161.08	164.40	1,786.20	3,111.68	1,201,108.48
		Excavation	1.20	cu.m			1,000.00	-	-	1,200.00		
		Sand	0.12	cu.m	1,850.00	370.00		222.00	44.40	-		
		RCP 300 mm dia.	1.00	pc	713.00	120.00		713.00	120.00	-		
		Soil Disposal	1.06	cu.m			500.00	-	-	531.00		
		Backfilling	0.14	cu.m			400.00	-	-	55.20		
		Plastering Joint	1.88	l.m	120.00			226.08	-	-		
		375mm Ø (15")	25.00	m				1,328.60	186.60	2,340.75	3,855.95	96,398.75
		Excavtion	1.58	cu.m	-	-	1,000.00	-	-	1,575.00		
		Sand	0.18	cu.m	1,850.00	370.00	-	333.00	66.60	-		
		RCP 375 mm dia.	1.00	pc	713.00	120.00	-	713.00	120.00	-		
		Soil Disposal	1.36	cu.m	-	-	500.00	-	-	678.75		
		Backfilling	0.22	cu.m	-	-	400.00	-	-	87.00		
		Plastering Joint	2.36	l.m	120.00	-	-	282.60	-	-		
		450mm Ø (18")	30.00	m				1,440.62	197.70	2,808.30	4,446.62	133,398.60
		Excavtion	1.89	cu.m	-	-	1,000.00	-	-	1,890.00		
		Sand	0.21	cu.m	1,850.00	370.00	-	388.50	77.70	-		
		RCP 450 mm dia.	1.00	pc	713.00	120.00	-	713.00	120.00	-		
		Soil Disposal	1.62	cu.m	-	-	500.00	-	-	811.50		
		Backfilling	0.27	cu.m	-	-	400.00	-	-	106.80		
		Plastering Joint	2.83	l.m	120.00	-	-	339.12	-	-		
		750mm Ø (30")	44.00	m				2,152.33	294.83	4,724.25	7,171.40	315,541.60
		Excavtion	3.17	cu.m	-	-	1,000.00	-	-	3,172.50		
		Sand	0.47	cu.m	1,850.00	370.00	-	874.13	174.83	-		
		RCP 450 mm dia.	1.00	pc	713.00	120.00	-	713.00	120.00	-		
		Soil Disposal	2.83	cu.m	-	-	500.00	-	-	1,413.75		
		Backfilling	0.34	cu.m	-	-	400.00	-	-	138.00		
		Plastering Joint	4.71	l.m	120.00	-	-	565.20	-	-		
		900mm Ø (36")	18.00	m				2,639.99	369.75	5,705.10	8,714.84	156,867.12
		Excavtion	3.83	cu.m	-	-	1,000.00	-	-	3,825.00		
		Sand	0.68	cu.m	1,850.00	370.00	-	1,248.75	249.75	-		
		RCP 450 mm dia.	1.00	pc	713.00	120.00	-	713.00	120.00	-		

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		Soil Disposal	3.50	cu.m	-	-	500.00	-	-	1,750.50		
		Backfilling	0.32	cu.m	-	-	400.00	-	-	129.60		
		Plastering Joint	5.65	l.m	120.00	-	-	678.24	-	-		
SS1	b.	Canals, Open or Closed	1	lot	N/A	N/A	N/A	N/A	N/A	N/A		
	c.	Drainage Appurtenant Structures	1.00	lot							582,673.30	582,673.30
		DI	1.00	each				18,288.17	2,895.88	3,216.98	24,401.04	24,401.04
		Excavation	1.80	cu.m	-	-	1,000.00	-	-	1,800.00		
		Lean Concrete 2000psi	0.04	cu.m	4,650.00	1,250.00	350.00	188.33	50.63	14.18		
		Concreting 3000psi	0.36	cu.m	6,500.00	1,250.00	350.00	2,349.75	451.88	126.53		
		Rebars	20.29	kgs	50.00	15.00	2.00	1,014.60	304.38	40.58		
		Formworks	5.34	sq.m	325.00	250.00	75.00	1,735.50	1,335.00	400.50		
		Backfilling	1.15	cu.m	-	-	500.00	-	-	576.00		
		Disposal	0.65	cu.m	-	-	400.00	-	-	259.20		
		Trench Cover	1.00	set	13,000.00	754.00		13,000.00	754.00	-		
		SI	1.00	each				10,017.24	3,753.25	6,394.99	20,165.47	20,165.47
		Excavation	3.74	cu.m	-	-	1,000.00	-	-	3,742.05		
		Lean Concrete 2000psi	0.11	cu.m	4,650.00	1,250.00	350.00	498.71	134.06	37.54		
		Concreting 3000psi	0.52	cu.m	6,500.00	1,250.00	350.00	3,388.13	651.56	182.44		
		Rebars	74.51	kg	50.00	15.00	2.00	3,725.40	1,117.62	149.02		
		Formworks	7.40	sq..m	325.00	250.00	75.00	2,405.00	1,850.00	555.00		
		Backfilling	2.33	cu.m	-	-	500.00	-	-	1,163.75		
		Disposal	1.41	cu.m	-	-	400.00	-	-	565.20		
		SI-CB	1.00	each				12,618.80	4,532.95	10,268.85	27,420.60	27,420.60
		Excavation	6.18	cu.m	-	-	1,000.00	-	-	6,184.50		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	376.65	101.25	28.35		
		Concreting 3000psi	0.96	cu.m	6,500.00	1,250.00	350.00	6,262.75	1,204.38	337.23		
		Rebars	58.49	kg	50.00	15.00	2.00	2,924.40	877.32	116.98		
		Formworks	9.40	sq.m	325.00	250.00	75.00	3,055.00	2,350.00	705.00		
		Backfilling	4.23	cu.m	-	-	500.00	-	-	2,115.00		
		Disposal	1.95	cu.m	-	-	400.00	-	-	781.80		
		JB	1.00	each				17,846.17	5,889.42	12,831.29	36,566.87	36,566.87
		Excavation	7.72	cu.m	-	-	1,000.00	-	-	7,723.40		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	392.93	105.63	29.58		

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		Concreting 3000psi	1.45	cu.m	6,500.00	1,250.00	350.00	9,413.69	1,810.33	506.89		
		Rebars	94.23	kg	50.00	15.00	2.00	4,711.55	1,413.47	188.46		
		Formworks	10.24	sq..m	325.00	250.00	75.00	3,328.00	2,560.00	768.00		
		Backfilling	5.26	cu.m	-	-	500.00	-	-	2,628.00		
		Disposal	2.47	cu.m	-	-	400.00	-	-	986.96		
		CHW	2.00	set				39,946.50	14,835.25	7,562.45	62,344.20	124,688.40
		Excavation	2.28	cu.m	-	-	1,000.00	-	-	2,276.50		
		Lean Concrete 2000psi	0.04	cu.m	4,650.00	1,250.00	350.00	204.60	55.00	15.40		
		Concreting 3000psi	3.54	cu.m	6,500.00	1,250.00	350.00	23,026.90	4,428.25	1,239.91		
		Rebars	106.80	kg	50.00	15.00	2.00	5,340.00	1,602.00	213.60		
		Formworks	35.00	sq..m	325.00	250.00	75.00	11,375.00	8,750.00	2,625.00		
		Backfilling	0.55	cu.m	-	-	500.00	-	-	275.00		
		Disposal	2.29	cu.m	-	-	400.00	-	-	917.04		
		Sump Pit	1.00	set				117,580.50	36,024.85	33,915.90	187,521.25	187,521.25
		Excavation	18.03	cu.m	-	-	1,000.00	-	-	18,025.25		
		Lean Concrete 2000psi	0.32	cu.m	4,650.00	1,250.00	350.00	1,472.89	395.94	110.86		
		Concreting 3000psi	8.15	cu.m	6,500.00	1,250.00	350.00	52,992.88	10,190.94	2,853.46		
		Rebars	299.86	kgs	50.00	15.00	2.00	14,993.24	4,497.97	599.73		
		Formworks	68.22	sq.m	325.00	250.00	75.00	22,171.50	17,055.00	5,116.50		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		
		Disposal	18.03	cu.m	-	-	400.00	-	-	7,210.10		
		Ladder Rung	7.00	cu.m	1,850.00	555.00	-	12,950.00	3,885.00	-		
		Manhole Cover	1.00	cu.m	13,000.00	-	-	13,000.00	-	-		
		SV Guardhouse	1.00	set				26,531.75	10,791.94	15,473.63	52,797.32	52,797.32
		Excavation	5.30	cu.m	-	-	1,000.00	-	-	5,304.00		
		Lean Concrete 2000psi	0.20	cu.m	4,650.00	1,250.00	350.00	948.60	255.00	71.40		
		Concreting 3000psi	1.87	cu.m	6,500.00	1,250.00	350.00	12,168.00	2,340.00	655.20		
		Rebars	90.46	kgs	50.00	15.00	2.00	4,523.15	1,356.94	180.93		
		Formworks	27.36	sq.m	325.00	250.00	75.00	8,892.00	6,840.00	2,052.00		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		
		Disposal	18.03	cu.m	-	-	400.00	-	-	7,210.10		
		SV Control Building	1.00	set				27,286.54	11,075.30	16,194.33	54,556.18	54,556.18
		Excavation	5.95	cu.m	-	-	1,000.00	-	-	5,950.00		
		Lean Concrete 2000psi	0.21	cu.m	4,650.00	1,250.00	350.00	988.13	265.63	74.38		
		Concreting 3000psi	1.92	cu.m	6,500.00	1,250.00	350.00	12,506.00	2,405.00	673.40		
		Rebars	93.98	kgs	50.00	15.00	2.00	4,698.92	1,409.68	187.96		
		Formworks	27.98	sq.m	325.00	250.00	75.00	9,093.50	6,995.00	2,098.50		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		
		Disposal	18.03	cu.m	-	-	400.00	-	-	7,210.10		
		SV Warehouse	1.00	set				27,286.54	11,075.30	16,194.33	54,556.18	54,556.18
		Excavation	5.95	cu.m	-	-	1,000.00	-	-	5,950.00		
		Lean Concrete 2000psi	0.21	cu.m	4,650.00	1,250.00	350.00	988.13	265.63	74.38		
		Concreting 3000psi	1.92	cu.m	6,500.00	1,250.00	350.00	12,506.00	2,405.00	673.40		
		Rebars	93.98	kgs	50.00	15.00	2.00	4,698.92	1,409.68	187.96		
		Formworks	27.98	sq.m	325.00	250.00	75.00	9,093.50	6,995.00	2,098.50		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		
		Disposal	18.03	cu.m	-	-	400.00	-	-	7,210.10		

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
	3.	**Gantry Structures (Lattice Type)**										
SS1	a.	138kV Gantry Structures	1.00	lot				-	516,074.67	-	516,074.67	516,074.67
		Beam	3,981.68	kgs	-	25.00	-	-	99,542.07	-		
		Post 3 leg	8,235.69	kgs	-	25.00	-	-	205,892.28	-		
		Post 2 leg	8,425.61	kgs	-	25.00	-	-	210,640.32	-		
	4.	**Equipment Steel Support Structures (Lattice Type)**										
SS1	a.	138kV Capacitive Voltage Transformer	1.00	lot				-	2,500.00	-	2,500.00	2,500.00
		Weight	100.00	kgs	-	25.00	-	-	2,500.00	-		
SS1	b.	138kV Surge Arrester	1.00	lot				-	2,500.00	-	2,500.00	2,500.00
		Weight	100.00	kgs	-	25.00	-	-	2,500.00	-		
SS1	c.	69kV Capacitive Voltage Transformer	1.00	lot				-	2,500.00	-	2,500.00	2,500.00
		Weight	100.00	kgs	-	25.00	-	-	2,500.00	-		
SS1	d.	69kV Combined Instrument Transformer (metering)	1.00	lot				-	2,500.00	-	2,500.00	2,500.00
		Weight	100.00	kgs	-	25.00	-	-	2,500.00	-		
SS1	e.	69 kV Power Shunt Capacitor (incl. Limiting Reactor, Surge Arrester & Neutral Current transformer)	1.00	lot				-	2,500.00	-	2,500.00	2,500.00
		Weight	100.00	kgs	-	25.00	-	-	2,500.00	-		
SS1	f.	69kV Surge Arrester	1.00	lot				-	2,500.00	-	2,500.00	2,500.00
		Weight	100.00	kgs	-	25.00	-	-	2,500.00	-		
SS1	g.	13.8kV Metering Equipment	1.00	lot				-	2,500.00	-	2,500.00	2,500.00
		Weight	100.00	kgs	-	25.00	-	-	2,500.00	-		
	5.	**Gantry Foundations, Isolated Dry (including anchor bolts)**										
SS1	a.	138kV Gantry Foundations	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m			1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m			500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m			400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00			15,000.00	-	-		
	6.	**Equipment Foundations, Isolated Dry**			N/A	N/A	N/A	N/A	N/A	N/A		
SS1	a.	138kV Capacitive Voltage Transformer (including anchor bolts)	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	b.	138kV Disconnect Switch	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	c.	138kV Disconnect Switch w/ Earthing Switch	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	d.	138kV Surge Arrester (including anchor bolts)	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	e.	69kV Capacitive Voltage Transformer (including anchor bolts) (Incl. separate Marshalling Box Foundation)	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
		Incl. Local Control Cabinet Foundation										
		Excavation	0.24	cu.m								
		Lean Concrete 2000psi	0.06	cu.m								
		Concreting 3000psi	0.61	cu.m								
		Rebars	58.29	kgs								
		Formworks	2.20	sq.m								
		Backfilling	-	cu.m								
		Soil Disposal	0.24	cu.m								

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
SS1	f.	69kV Combined Instrument Transformer (metering)	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	g.	69 kV Power Shunt Capacitor (including anchor bolts)	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	h.	69kV Surge Arrester (including anchor bolts)	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	i.	13.8kV Metering Equipment	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	j.	Marshalling Box Foundation (for existing CT and VT)	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	k.	AC Sub-Distribution Outdoor Panel Foundation	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	l.	DC Sub-Distribution Outdoor Panel Foundation	1.00	lot				136,286.84	33,518.74	49,226.62	219,032.21	219,032.21
		Excavation	28.79	cu.m	-	-	1,000.00	-	-	28,787.50		
		Lean Concrete 2000psi	0.61	cu.m	4,650.00	1,250.00	350.00	2,848.13	765.63	214.38		
		Concreting 3000psi	7.15	cu.m	6,500.00	1,250.00	350.00	46,475.00	8,937.50	2,502.50		
		Rebars	752.37	kgs	50.00	15.00	2.00	37,618.72	11,285.62	1,504.75		
		Formworks	14.60	sq.m	325.00	250.00	75.00	4,745.00	3,650.00	1,095.00		
		Backfilling	21.28	cu.m	-	-	500.00	-	-	10,637.50		
		Soil Disposal	7.51	cu.m	-	-	400.00	-	-	3,005.00		
		M36 - 1280mm	8.00	pc	3,700.00	1,110.00	185.00	29,600.00	8,880.00	1,480.00		
		Non-Shrink Grout	0.20	cu.m	75,000.00	-	-	15,000.00	-	-		
SS1	m.	Smart Outdoor Panel Enclosure Foundation, Type 1	1.00	lot				20,956.97	5,357.78	3,595.66	29,910.41	29,910.41
		Excavation	1.69	cu.m	-	-	1,000.00	-	-	1,690.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	392.93	105.63	29.58		
		Concreting 3000psi	1.23	cu.m	6,500.00	1,250.00	350.00	7,991.75	1,536.88	430.33		
		Rebars	165.02	kgs	50.00	15.00	2.00	8,250.92	2,475.28	330.04		
		Formworks	4.96	sq.m	325.00	250.00	75.00	1,612.00	1,240.00	372.00		
		Backfilling	0.68	cu.m	-	-	500.00	-	-	338.63		
		Soil Disposal	1.01	cu.m	-	-	400.00	-	-	405.10		
		Non-Shrink Grout	0.04	cu.m	75,000.00	-	-	2,709.38	-	-		
SS1	n.	Smart Outdoor Panel Enclosure Foundation, Type 2	1.00	lot				20,956.97	5,357.78	3,595.66	29,910.41	29,910.41
		Excavation	1.69	cu.m	-	-	1,000.00	-	-	1,690.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	392.93	105.63	29.58		
		Concreting 3000psi	1.23	cu.m	6,500.00	1,250.00	350.00	7,991.75	1,536.88	430.33		
		Rebars	165.02	kgs	50.00	15.00	2.00	8,250.92	2,475.28	330.04		
		Formworks	4.96	sq.m	325.00	250.00	75.00	1,612.00	1,240.00	372.00		
		Backfilling	0.68	cu.m	-	-	500.00	-	-	338.63		
		Soil Disposal	1.01	cu.m	-	-	400.00	-	-	405.10		
		Non-Shrink Grout	0.04	cu.m	75,000.00	-	-	2,709.38	-	-		
SS1	**7.**	**Slope Protection**										
SS1	a.	Grouted Rockwall	1	lot	N/A	N/A	N/A	N/A	N/A	N/A		
SS1	b.	Reinforced Concrete Retaining Wall	1	lot	N/A	N/A	N/A	N/A	N/A	N/A		
SS1	**8.**	**Cable Trench for XLPE Underground Power Cables**			N/A	N/A	N/A	N/A	N/A	N/A		
SS1	a.	138 kV XLPE Underground Power Cables	1	lot	N/A	N/A	N/A	N/A	N/A	N/A		
SS1	b.	69 kV XLPE Underground Power Cables	1	lot								
SS1	**9.**	**Concrete Water Tank (170 cu.m)**	1	lot								

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
	C.2	**COMPLETE FURNISH, INSTALL, CONSTRUCT, SUPPLY, PROVIDE, ERECT, PLACE, APPLY AND/OR LAY INCLUDING FURNISHING OF ALL PLANT, LABOR, EQUIPMENT AND MATERIALS OF THE FOLLOWING ITEMS OF WORKS IN ACCORDANCE WITH THE PROVISIONS IN THE TECHNICAL SPECIFICATIONS/BIDDING DOCUMENTS. ALL WORKS SHALL BE IN COMPLIANCE WITH NGCP CONSTRUCTION QUALITY AND WORKMANSHIP STANDARD:**										
	1.	**Roadways**										
SS1	a.	6.0M Wide Concrete Roadway	1.00	lot				9,665.64	2,780.38	3,708.55	16,154.57	16,154.57
		Rebars Works	6.28	kg	50.00	15.00	2.00	313.78	94.13	12.55		
		Formworks	3.00	length	200.00	120.00	-	600.00	360.00	-		
		ReadyMix 3000PSI	1.20	cu.m.	6,500.00	1,250.00	350.00	7,800.00	1,500.00	420.00		
		Basecourse	0.90	cu.m.	850.00	85.00	340.00	765.00	76.50	306.00		
		Compaction	6.00	sq.m.			350.00	-	-	2,100.00		
		Concrete Cutting	4.50	l.m.		150.00	60.00	-	675.00	270.00		
		Expansion Joint						-	-	-		
		Bituminus Seal	0.03	bags	5,080.00	2,032.00		152.40	60.96	-		
		Upvc Pipe 3/4 dia.	0.13	pc	269.00	107.60		34.47	13.79	-		
		Soil Grading	6.00	sq.m			100.00	-	-	600.00		
SS1	b.	5.0M Wide Concrete Roadway	1.00	lot				9,665.64	2,780.38	3,708.55	16,154.57	16,154.57
		Rebars Works	6.28	kg	50.00	15.00	2.00	313.78	94.13	12.55		
		Formworks	3.00	length	200.00	120.00	-	600.00	360.00	-		
		ReadyMix 3000PSI	1.20	cu.m.	6,500.00	1,250.00	350.00	7,800.00	1,500.00	420.00		
		Basecourse	0.90	cu.m.	850.00	85.00	340.00	765.00	76.50	306.00		
		Compaction	6.00	sq.m.			350.00	-	-	2,100.00		
		Concrete Cutting	4.50	l.m.		150.00	60.00	-	675.00	270.00		
		Expansion Joint						-	-	-		
		Bituminus Seal	0.03	bags	5,080.00	2,032.00		152.40	60.96	-		
		Upvc Pipe 3/4 dia.	0.13	pc	269.00	107.60		34.47	13.79	-		
		Soil Grading	6.00	sq.m			100.00	-	-	600.00		
SS1	c.	3.0M Wide Concrete Roadway	1.00	lot				9,665.64	2,780.38	3,708.55	16,154.57	16,154.57
		Rebars Works	6.28	kg	50.00	15.00	2.00	313.78	94.13	12.55		
		Formworks	3.00	length	200.00	120.00	-	600.00	360.00	-		
		ReadyMix 3000PSI	1.20	cu.m.	6,500.00	1,250.00	350.00	7,800.00	1,500.00	420.00		
		Basecourse	0.90	cu.m.	850.00	85.00	340.00	765.00	76.50	306.00		
		Compaction	6.00	sq.m.			350.00	-	-	2,100.00		
		Concrete Cutting	4.50	l.m.		150.00	60.00	-	675.00	270.00		
		Expansion Joint						-	-	-		
		Bituminus Seal	0.03	bags	5,080.00	2,032.00		152.40	60.96	-		
		Upvc Pipe 3/4 dia.	0.13	pc	269.00	107.60		34.47	13.79	-		
		Soil Grading	6.00	sq.m			100.00	-	-	600.00		
SS1	d.	Concrete Curb and Gutter	1.00	lot				1,238.94	336.18	294.79	1,869.91	1,869.91
		Rebars Works	5.23	kg	50.00	15.00	2.00	261.44	78.43	10.46		
		Formworks	1.00	sq.m	200.00	120.00	-	200.00	120.00	-		
		ReadyMix 3000PSI	0.10	cu.m.	6,500.00	1,250.00	350.00	650.00	125.00	35.00		
		Basecourse	0.15	cu.m	850.00	85.00	340.00	127.50	12.75	51.00		
		Compaction	0.57	sq.m	-	-	350.00	-	-	198.33		
SS1	e.	Concrete Sidewalk	1	lot				1,238.94	336.18	494.79	2,069.91	2,069.91

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		Excavation	0.20	cu.m.			1,000.00	-	-	200.00		
		Rebars Works	5.23	kg	50.00	15.00	2.00	261.44	78.43	10.46		
		Formworks	1.00	sq.m	200.00	120.00	-	200.00	120.00	-		
		ReadyMix 3000PSI	0.10	cu.m.	6,500.00	1,250.00	350.00	650.00	125.00	35.00		
		Basecourse	0.15	cu.m	850.00	85.00	340.00	127.50	12.75	51.00		
		Compaction	0.57	sq.m	-	-	350.00	-	-	198.33		
SS1	f.	Concrete Pavement / Open Stockyard	1	lot				1,238.94	336.18	494.79	2,069.91	2,069.91
		Excavation	0.20	cu.m.			1,000.00	-	-	200.00		
		Rebars Works	5.23	kg	50.00	15.00	2.00	261.44	78.43	10.46		
		Formworks	1.00	sq.m	200.00	120.00	-	200.00	120.00	-		
		ReadyMix 3000PSI	0.10	cu.m.	6,500.00	1,250.00	350.00	650.00	125.00	35.00		
		Basecourse	0.15	cu.m	850.00	85.00	340.00	127.50	12.75	51.00		
		Compaction	0.57	sq.m	-	-	350.00	-	-	198.33		
	2.	**Cable Trenches (including steel plate cover)**										
SS1	a.	CT-SS4S	1.00	lot				9,689.65	3,324.52	5,694.44	18,708.61	18,708.61
		Excavation	3.38	cu.m	-	-	1,000.00	-	-	3,375.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	348.75	93.75	26.25		
		Concreting 3000psi	0.70	cu.m	6,500.00	1,250.00	350.00	4,517.50	868.75	243.25		
		Rebars	57.47	kgs	50.00	15.00	2.00	2,873.40	862.02	114.94		
		Formworks	6.00	sq.m	325.00	250.00	75.00	1,950.00	1,500.00	450.00		
		Backfilling	1.35	cu.m	-	-	500.00	-	-	675.00		
		Soil Disposal	2.03	cu.m	-	-	400.00	-	-	810.00		
SS1	b.	CT-RSC2	1.00	lot				9,689.65	3,324.52	5,694.44	18,708.61	18,708.61
		Excavation	3.38	cu.m	-	-	1,000.00	-	-	3,375.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	348.75	93.75	26.25		
		Concreting 3000psi	0.70	cu.m	6,500.00	1,250.00	350.00	4,517.50	868.75	243.25		
		Rebars	57.47	kgs	50.00	15.00	2.00	2,873.40	862.02	114.94		
		Formworks	6.00	sq.m	325.00	250.00	75.00	1,950.00	1,500.00	450.00		
		Backfilling	1.35	cu.m	-	-	500.00	-	-	675.00		
		Soil Disposal	2.03	cu.m	-	-	400.00	-	-	810.00		
SS1	c.	CT-DS2S	1.00	lot				9,689.65	3,324.52	5,694.44	18,708.61	18,708.61
		Excavation	3.38	cu.m	-	-	1,000.00	-	-	3,375.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	348.75	93.75	26.25		
		Concreting 3000psi	0.70	cu.m	6,500.00	1,250.00	350.00	4,517.50	868.75	243.25		
		Rebars	57.47	kgs	50.00	15.00	2.00	2,873.40	862.02	114.94		
		Formworks	6.00	sq.m	325.00	250.00	75.00	1,950.00	1,500.00	450.00		
		Backfilling	1.35	cu.m	-	-	500.00	-	-	675.00		
		Soil Disposal	2.03	cu.m	-	-	400.00	-	-	810.00		
SS1	d.	CT-DS4S	1.00	lot				9,689.65	3,324.52	5,694.44	18,708.61	18,708.61
		Excavation	3.38	cu.m	-	-	1,000.00	-	-	3,375.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	348.75	93.75	26.25		
		Concreting 3000psi	0.70	cu.m	6,500.00	1,250.00	350.00	4,517.50	868.75	243.25		
		Rebars	57.47	kgs	50.00	15.00	2.00	2,873.40	862.02	114.94		
		Formworks	6.00	sq.m	325.00	250.00	75.00	1,950.00	1,500.00	450.00		
		Backfilling	1.35	cu.m	-	-	500.00	-	-	675.00		
		Soil Disposal	2.03	cu.m	-	-	400.00	-	-	810.00		
SS1	e.	CT-DS4R	1.00	lot				9,689.65	3,324.52	5,694.44	18,708.61	18,708.61

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		Excavation	3.38	cu.m	-	-	1,000.00	-	-	3,375.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	348.75	93.75	26.25		
		Concreting 3000psi	0.70	cu.m	6,500.00	1,250.00	350.00	4,517.50	868.75	243.25		
		Rebars	57.47	kgs	50.00	15.00	2.00	2,873.40	862.02	114.94		
		Formworks	6.00	sq.m	325.00	250.00	75.00	1,950.00	1,500.00	450.00		
		Backfilling	1.35	cu.m	-	-	500.00	-	-	675.00		
		Soil Disposal	2.03	cu.m	-	-	400.00	-	-	810.00		
SS1	f.	CPCR(3 Pipes)	1.00	lot				9,689.65	3,324.52	5,694.44	18,708.61	18,708.61
		Excavation	3.38	cu.m	-	-	1,000.00	-	-	3,375.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	348.75	93.75	26.25		
		Concreting 3000psi	0.70	cu.m	6,500.00	1,250.00	350.00	4,517.50	868.75	243.25		
		Rebars	57.47	kgs	50.00	15.00	2.00	2,873.40	862.02	114.94		
		Formworks	6.00	sq.m	325.00	250.00	75.00	1,950.00	1,500.00	450.00		
		Backfilling	1.35	cu.m	-	-	500.00	-	-	675.00		
		Soil Disposal	2.03	cu.m	-	-	400.00	-	-	810.00		
SS1	g.	Concrete Pullbox	1.00	lot				9,689.65	3,324.52	5,694.44	18,708.61	18,708.61
		Excavation	3.38	cu.m	-	-	1,000.00	-	-	3,375.00		
		Lean Concrete 2000psi	0.08	cu.m	4,650.00	1,250.00	350.00	348.75	93.75	26.25		
		Concreting 3000psi	0.70	cu.m	6,500.00	1,250.00	350.00	4,517.50	868.75	243.25		
		Rebars	57.47	kgs	50.00	15.00	2.00	2,873.40	862.02	114.94		
		Formworks	6.00	sq.m	325.00	250.00	75.00	1,950.00	1,500.00	450.00		
		Backfilling	1.35	cu.m	-	-	500.00	-	-	675.00		
		Soil Disposal	2.03	cu.m	-	-	400.00	-	-	810.00		
SS1	**3.**	**Seclusion Fence and Gates**	1	lot								
	4.	**Oil-Water Separation System**										
SS1	a.	Oil-Water Separation System for Waste Management House - 1 unit of oil-water separator tank including all inlet pipes	1	lot				38,242.56	13,239.48	8,864.89	60,346.94	60,346.94
		Excavation	4.11	cu.m	-	-	1,000.00	-	-	4,108.25		
		Lean Concrete 2000psi	0.12	cu.m	4,650.00	1,250.00	350.00	569.63	153.13	42.88		
		Concreting 3000psi	1.71	cu.m	6,500.00	1,250.00	350.00	11,117.93	2,138.06	598.66		
		Rebars	118.05	kgs	50.00	15.00	2.00	5,902.75	1,770.82	236.11		
		Formworks	28.59	sq.m	325.00	250.00	75.00	9,291.43	7,147.25	2,144.18		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		
		Soil Disposal	4.11	cu.m	-	-	400.00	-	-	1,643.30		
		3mm THK. Stainless Steel	0.13	pc	14,644.35	4,393.31	732.22	1,830.54	549.16	91.53		
		100mm Black Iron Outlet Pipe	0.50	pc	7,602.00	760.20	-	3,801.00	380.10	-		
		Steel Cover			-	-	-	-	-	-		
		50mmx50mmx6mm	26.66	kgs	125.00	24.00	-	3,332.50	639.84	-		
		10mm Anchor	2.34	kgs	125.00	24.00	-	292.95	56.25	-		
		5mm THK. Checkered Plate	15.90		125.00	24.00	-	1,987.03	381.51	-		
		12mm Lift Bar Handle	0.93	kgs	125.00	25.00	-	116.81	23.36	-		
SS1	b.	Oil-Water Separation System for Chemical Storage Facility - 1 unit of oil-water separator tank including all inlet pipes	1	lot				38,242.56	13,239.48	8,864.89	60,346.94	60,346.94
		Excavation	4.11	cu.m	-	-	1,000.00	-	-	4,108.25		
		Lean Concrete 2000psi	0.12	cu.m	4,650.00	1,250.00	350.00	569.63	153.13	42.88		
		Concreting 3000psi	1.71	cu.m	6,500.00	1,250.00	350.00	11,117.93	2,138.06	598.66		
		Rebars	118.05	kgs	50.00	15.00	2.00	5,902.75	1,770.82	236.11		
		Formworks	28.59	sq.m	325.00	250.00	75.00	9,291.43	7,147.25	2,144.18		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		Soil Disposal	4.11	cu.m	-	-	400.00	-	-	1,643.30		
		3mm THK. Stainless Steel	0.13	pc	14,644.35	4,393.31	732.22	1,830.54	549.16	91.53		
		100mm Black Iron Outlet Pipe	0.50	pc	7,602.00	760.20	-	3,801.00	380.10	-		
		Steel Cover			-	-	-	-	-	-		
		50mmx50mmx6mm	26.66	kgs	125.00	24.00	-	3,332.50	639.84	-		
		10mm Anchor	2.34	kgs	125.00	24.00	-	292.95	56.25	-		
		5mm THK. Checkered Plate	15.90		125.00	24.00	-	1,987.03	381.51	-		
		12mm Lift Bar Handle	0.93	kgs	125.00	25.00	-	116.81	23.36	-		
SS1	c.	Oil-Water Separation System for Genset House - 1 unit of oil-water separator tank including all inlet and discharge pipes	1	lot				38,242.56	13,239.48	8,864.89	60,346.94	60,346.94
		Excavation	4.11	cu.m	-	-	1,000.00	-	-	4,108.25		
		Lean Concrete 2000psi	0.12	cu.m	4,650.00	1,250.00	350.00	569.63	153.13	42.88		
		Concreting 3000psi	1.71	cu.m	6,500.00	1,250.00	350.00	11,117.93	2,138.06	598.66		
		Rebars	118.05	kgs	50.00	15.00	2.00	5,902.75	1,770.82	236.11		
		Formworks	28.59	sq.m	325.00	250.00	75.00	9,291.43	7,147.25	2,144.18		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		
		Soil Disposal	4.11	cu.m	-	-	400.00	-	-	1,643.30		
		3mm THK. Stainless Steel	0.13	pc	14,644.35	4,393.31	732.22	1,830.54	549.16	91.53		
		100mm Black Iron Outlet Pipe	0.50	pc	7,602.00	760.20	-	3,801.00	380.10	-		
		Steel Cover			-	-	-	-	-	-		
		50mmx50mmx6mm	26.66	kgs	125.00	24.00	-	3,332.50	639.84	-		
		10mm Anchor	2.34	kgs	125.00	24.00	-	292.95	56.25	-		
		5mm THK. Checkered Plate	15.90		125.00	24.00	-	1,987.03	381.51	-		
		12mm Lift Bar Handle	0.93	kgs	125.00	25.00	-	116.81	23.36	-		
SS1	d.	Oil-Water Separation System for Existing Temporary PTR Foundations - 1 unit of oil-water separator tank including all inlet and discharge pipes	1	lot				72,418.43	25,572.11	17,802.07	115,792.61	115,792.61
		Excavation	8.36	cu.m	-	-	1,000.00	-	-	8,360.00		
		Lean Concrete 2000psi	1.42	cu.m	4,650.00	1,250.00	350.00	6,607.65	1,776.25	497.35		
		Concreting 3000psi	2.92	cu.m	6,500.00	1,250.00	350.00	18,974.15	3,648.88	1,021.69		
		Rebars	242.30	kgs	50.00	15.00	2.00	12,114.90	3,634.47	484.60		
		Formworks	52.76	sq.m	325.00	250.00	75.00	17,147.65	13,190.50	3,957.15		
		Backfilling	-	cu.m	-	-	500.00	-	-	-		
		Soil Disposal	8.36	cu.m	-	-	400.00	-	-	3,344.00		
		3mm THK. Stainless Steel	0.19	pc	14,644.35	4,393.31	732.22	2,745.82	823.74	137.29		
		100mm Black Iron Outlet Pipe	0.50	pc	7,602.00	760.20		3,801.00	380.10	-		
		Steel Cover						-	-	-		
		50mmx50mmx6mm	37.84	kgs	125.00	24.00		4,730.00	908.16	-		
		10mm Anchor	2.34	kgs	125.00	24.00		292.95	56.25	-		
		5mm THK. Checkered Plate	47.10	kgs	125.00	24.00		5,887.50	1,130.40	-		
		12mm Lift Bar Handle	0.93	kgs	125.00	25.00		116.81	23.36	-		
SS1	**5.**	**Sentry Tower (Structure and Foundation)**	1	lot				599,477.46	262,165.15	114,861.09	976,503.70	976,503.70
		Excavation	15.95	cu.m	-	-	1,000.00	-	-	15,950.00		
		Lean Concrete 2000psi	3.85	cu.m	4,650.00	1,250.00	350.00	17,884.48	4,807.66	1,346.14		
		Concreting 3000psi	6.86	cu.m	6,500.00	1,250.00	350.00	44,588.38	8,574.69	2,400.91		
		Rebars	1,002.60	kgs	50.00	15.00	2.00	50,130.00	15,039.00	2,005.20		
		Formworks	26.36	sq.m	325.00	250.00	75.00	8,567.00	6,590.00	1,977.00		
		Backfilling	10.84	cu.m	-	-	500.00	-	-	5,419.50		
		Soil Disposal	5.11	cu.m	-	-	400.00	-	-	2,044.40		
		M24- 885mm	16.00	pc	1,350.00	-	500.00	21,600.00	-	8,000.00		
		Non-Shrink Grout	0.03	cu.m	75,000.00	-	-	2,400.00	-	-		

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)
		Steel Structure	1.00	lot	454,307.60	227,153.80	75,717.93	454,307.60	227,153.80	75,717.93		
SS1	6.	**New Gravel Surfacing**	1.00	lot	1,350.00	1,250.00	350.00	1,350.00	1,250.00	350.00	2,950.00	2,950.00
	C.3	**FURNISHING OF MATERIALS, LABOR, EQUIPMENT AND TOOLS FOR THE DEMOLITION/ CHIPPING-OFF / DISMANTLING/ MODIFICATION/ REMOVAL/ STRIPPING/ RELAYING OF EXISTING GRAVEL SURFACING / DISPOSAL AND RESTORATION WORKS OF EXISTING STRUCTURES AND ALL OTHER STRUCTURES AFFECTED BY THE CONSTRUCTION OF THE SUBSTATION. ALL WORKS SHALL BE IN COMPLIANCE WITH NGCP CONSTRUCTION QUALITY AND WORKMANSHIP STANDARD:**						-	-	-		
SS1	1.	Demolition, chipping-off, restoration and relocation (if any) of existing concrete roadway, curb and gutter, sidewalk / pathway / stairs, light posts, CHB fence, gate, slope protection, drainage appurtenant structures, and all other existing civil structures including other works necessary for the successful completion of the project.	1	lot				-	-	-		
SS1	2.	Dismantling, sorting / packing / crating / stockpiling and hauling of existing 69kV gantry steel structures, 69kV & 138kV equipment steel support structures, including interim BS & DS steel structures as well as by-pass structures (H-Frame) installed during Stage 1: Interim Scheme Works, and all other steel structures not clearly shown but affected by the project upgrading works.	1	lot								
SS1	3.	Demolition, uprooting, disposal, removal, backfilling, and grading of existing 69kV gantry foundations, existing 138kV & 69kV equipment support foundations, PTR foundation, including interim BS & DS support foundation installed during Stage 1: Interim Scheme Works, and all other foundation structures not clearly shown but affected by the project upgrading works.	1	lot								
SS1	4.	Demolition, dismantling, uprooting, removal, disposal, grading portion of existing seclusion fence around existing 69kV switchyard and 138kV switchyard.	1	lot								
SS1	5.	Demolition / chipping-off, disposal, restoration of existing cable trench to interconnect new cable trench and portion of new cable trench included in Stage 1: Interim Scheme Works	1	lot								
SS1	6.	Demolition, dismantling, removal, disposal, grading of existing guardhouse, pump house, watch tower, hazardous waste facility, chemical storage facility, fuel & chemical shed, and guest house (including foundation, appurtenances, electro-mechanical and other existing installations).	1	lot								
SS1	7.	Hauling, relocation, sorting, stockpiling, arrangement of items in the inventory list of stocks at Panitan Substation to the designated area at San Jose Substation.	1	lot								
SS1	8.	Stripping, removal, disposal of gravel surfacing within the existing 69kV and 138kV switchyard affected by the project upgrading works.	1	lot								
SS1	9.	Chipping-off, restoration, construction of new drainage around the Existing Temporary PTR Foundations near control building going to new Oil-Water Separator Tank.	1	lot								
SS1	10.	All other existing structures to be demolished / dismantled / removed / relocated / restored affected by the substation construction and all other miscellaneous works that may be deemed required for the successful completion of the project.	1	lot								
		TOTAL FOR CIVILWORKS (C)										

Note: Bid Prices shall be rounded to two (2) decimal places.

Legend:

a. For Plant and equipment (including spares, spare parts and tools) to be supplied from outside the Philippines, prices

ENGINEERING DESIGN DEPARTMENT

BID PRICE SCHEDULE

ASSET CODE	Item no.	Description	Qty/	Unit	UNIT PRICE			TOTAL PRICE			TOTAL UNIT PRICE	TOTAL PRICE
								(e)	(f)	(g)	(h)	(i)
			(a)		(b)	(c)	(d)	(a) x (b)	(a) x (ec)	(a) x (d)	Sum (e+f+g)	(a) x (h)

b. Receipt and Delivery of Plant and equipment under item (a) from the Port of Delivery to the designated job or project site under Scope of Works in the Technical Documents, prices shall be quoted inclusive of Load Port Survey Report

i. Value Added Tax (VAT) on importation

ii. Import Processing Fee (IPF)

iii. Container Security Fee (CSF)

c. For Plant and equipment (including spares, spare parts and tools) to be supplied from within the Philippines, prices shall be quoted including delivery to the designated job or project sites specified under Scope of Works in the

d. Erection / Installation / Civil Works / Testing / Commissioning / Trainings and other Services to be performed in the Philippines, identified in the Bidding Documents as necessary for the completion of the project shall be include proces